

## **Road Reconstruction — Caddy Avenue**

### **PROJECT:**

This project provides for road reconstruction works in Caddy Avenue from Fairway Drive for a distance of approximately 200m towards Tee Way.

The road reconstruction works are being undertaken as a result of inspections carried out as part of Council's ongoing asset inspection program which identified that the road was showing signs of pavement failure and distress.

#### **PROJECT ESTIMATE:**

\$700,000 (this project is funded through the Australian Government's Roads to Recovery Program)



The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

INDICATIVE PROJECT MILESTONES	
May 2020	Final Design
June/Aug 2020	Tender Period
Aug/Oct 2020	Construction Period
Nov 2020	Project Completion

Note: Project milestones are subject to contract and weather and may change.

#### **PROJECT SCOPE OF WORKS:**

The Project scope is as follows:

- Earthworks and excavation;
- Narrowing of road pavement area from the existing 12.5m carriage width to a new 11.0m carriage width;
- Placement of new pavement material;
- Replacement of kerb and channel on both sides;
- New stormwater drainage ;
- Replacement of existing stormwater drainage pits;
- Subsoil drainage;
- Bitumen/asphalt surfacing;
- Driveway extensions to suit new kerb alignment;
- Top dressing and turfing of disturbed areas.

# **INFRASTRUCTURE SERVICES**





