

Construction of Pedestrian Bridge—Urraween Road (between Maryborough Hervey Bay Road and Pantlins Lane)

PROJECT:

This project provides for the construction of a prefabricated steel truss bridge with fibre reinforced plastic decking to span an open drain and connect to a future concrete footpath in Urraween Road, Hervey Bay.

The design and construction project forms part of Council’s improvement of pedestrian infrastructure along Urraween Road, Hervey Bay and is supported by the Queensland Government’s Cycle Network Local Government Grants program.

PROJECT ESTIMATE:

\$160,000

PROJECT SCOPE OF WORKS:

The Project scope is as follows:

- Design, fabrication and installation of the pedestrian bridge including construction of abutments and piers;
- Reinstatement of affected areas including turfing and scour protection.



The pedestrian traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

INDICATIVE PROJECT MILESTONES

Mid March 2021	Final Design
March/April 2021	Fabrication
May 2021	Construction Period
June 2021	Project Completion

Note: Project milestones are subject to contract and weather and may change.