

Sectional Kerb and Channel and Footpath Replacement George Street

PROJECT:

This project provides for the replacement of approximately 35m of kerb and channel and footpath on the western side of George Street between 15 and 19 George Street.

The kerb and channel and footpath replacement works are being undertaken as a result of inspections carried out as part of Council's ongoing asset inspection program which identified that the kerb and channel and footpath was showing signs of failure and distress.

PROJECT ESTIMATE:

\$12,000

PROJECT SCOPE OF WORKS:

The Project scope is as follows:

- Excavation and earthworks;
- Concrete kerb and channel and footpath works;
- Replacement of driveway crossover at 17 George Street;
- Topdressing and turfing of disturbed areas



The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

INDICATIVE PROJECT MILESTONES

INDICATIVE PROJECT MILESTONES	
Aug 2021	Final Design
Aug/Sept 2021	Construction Period
Sept 2021	Project Completion

Note: Project milestones are subject to weather and may change.