

## Kerb and Channel Replacement and Pavement Works — Gillhespy Street (Bedford Street to Victory Street)

### PROJECT:

This project provides for the replacement of the existing kerb and channel and pavement reinstatement works on both sides of Gillhespy Street from Bedford Street to Victory Street. Works also include the installation of new stormwater drainage pipes, subsoil drainage works, asphalt surfacing and driveway extensions to suit the new kerb alignment.

The works are being undertaken as a result of inspections carried out as part of Council’s ongoing asset inspection program which identified that the kerb and channel was showing signs of failure and distress.

### PROJECT ESTIMATE:

\$727,000

### PROJECT SCOPE OF WORKS:

- Removal and disposal of the existing kerb and channel;
- Earthworks and stormwater pit replacements with associated drainage works;
- Construction of new kerb and channel and pavement reinstatement;
- Reinstatement of driveway crossovers and kerb ramps (reinstatement works to be completed in plain concrete only);
- Reinstatement of disturbed verges.



The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.

### INDICATIVE PROJECT MILESTONES

July 2021	Final Design
Oct/Jan 2022	Construction Period
Feb 2022	Project Completion

**Note:** Project milestones are subject to weather and may change.

# Kerb and Channel Replacement and Pavement Works — Gillhespy Street

## (Bedford Street to Victory Street)

