

## Kerb and Channel Replacement — Frank Street (Cheapside Street to Pallas Street)

### PROJECT:

This project provides for the replacement of the existing kerb and channel and pavement reinstatement works on the southern side of Frank Street between Cheapside Street and Pallas Street.

The works are being undertaken as a result of inspections carried out as part of Council’s ongoing asset inspection program which identified that the kerb and channel was showing signs of failure and distress.

### PROJECT ESTIMATE:

\$130,000

### PROJECT SCOPE OF WORKS:

- Removal and disposal of the existing kerb and channel;
- Construction of new kerb and channel and pavement reinstatement;
- Reconstruction of 7 x vehicle crossovers (*reinstatement works will be completed in plain concrete only*)
- Replacement of 2 gully boxes;
- Reinstatement of disturbed verges.



The traffic management plan that will be put in place for the duration of the construction period plans for a full road closure (local traffic only) traffic arrangement.

### INDICATIVE PROJECT MILESTONES

January 2022	Final Design
Feb/April 2022	Construction Period
April 2022	Project Completion

Note: Project milestones are subject to weather and may change.