

# FACT SHEET

May 2023

## Road Reconstruction—Walker Street (Pallas Street to Ferry Street)

### PROJECT:

This project provides for road reconstruction works in Walker Street between Pallas Street and Ferry Street.

This project was identified for completion as part of Council’s road reconstruction prioritisation process due to the road’s current condition level.

### PROJECT ESTIMATE:

\$3.8M (this project is partly funded through the State Government’s Transport Infrastructure Development Scheme)

### PROJECT SCOPE OF WORKS:

- Excavation and earthworks;
- Pavement rehabilitation works including new asphalt surfacing;
- Replacement of existing kerb and channel;
- Construction of a new 2m wide concrete footpath on the northern side of Walker Street and replacement of the existing footpath with a 1.5m concrete footpath on the southern side of Walker Street between Pallas Street and Ferry Street;
- Reconstruction of existing driveways to the property boundary and vehicle crossovers located at the following locations;

Concrete commercial driveways and vehicle crossovers at 72-74, 78 and 92 Walker Street and 170 Ferry Street.  
Concrete residential driveways and vehicle crossovers at 76, 79, 80, 81, 82, 84, 85, 86, 87, 88, 89, 91, 94, 96, 98, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 111, 113 and 115 Walker Street, 157 and 168 Tooley Street;

*(reinstatement works will be completed in plain concrete only)*



### PROJECT SCOPE OF WORKS (CONTD)

- Kerb ramps;
- Stormwater drainage works;
- Tree removals at 79, 87, 101, 106, 107 and 109 Walker Street with replacement plantings to be undertaken at 81, 91, 93 101, 103, 107, 109 and 113 Walker Street;
- New pedestrian refuge in Tooley Street;
- Upgrade of lighting in this section of Walker Street;
- Linemarking, topdressing and turfing of disturbed areas.

The traffic management plan that will be put in place for the duration of the construction period will allow for Walker Street to remain open at all times, with a one lane one-way traffic arrangement with traffic travelling in a westerly direction.

### INDICATIVE PROJECT MILESTONES

September 2022	Final Design
Sept/Nov 2022	Tender Period
June 2023/Feb 2024	Construction Period
March 2024	Project Completion

Note: Project milestones are subject to contract and weather and may change.

# Road Reconstruction—Walker Street (Pallas Street to Ferry Street)

