

Kerb and Channel and Footpath Replacement – Woodrow Street and Saltwater Creek Road (Wilson Street to 118 Saltwater Creek Road)

PROJECT:

This project provides for the replacement of the kerb and channel on the northern side of Woodrow Street from Wilson Street to Saltwater Creek Road and on the western side of Saltwater Creek Road from Woodrow Street to 118 Saltwater Creek Road. The project also provides for the replacement of the footpath in Saltwater Creek Road from Woodrow Street to 112 Saltwater Creek Road.

The works are being undertaken as a result of inspections carried out as part of Council's ongoing asset inspection program which identified that the kerb and channel and footpath was showing signs of failure and distress.

PROJECT ESTIMATE:

\$510,000 (this project is funded through the State Government's Works for Queensland Funding Program)

PROJECT SCOPE OF WORKS:

The project scope is as follows:

- Excavation and earthworks;
- Replacement of existing kerb and channel on the northern side of Woodrow Street from Wilson Street to Saltwater Creek Road and on the western side of Saltwater Creek Road from Woodrow Street to 118 Saltwater Creek Road;
- Reconstruction of 11 existing vehicle crossovers at 5, 7, 9, 11, 13, 15 and 19 Woodrow Street and 110 Saltwater Creek Road, 114 and 116 Saltwater Creek Road (joint vehicle crossover), and 112 and 118 Saltwater Creek Road (commercial vehicle crossovers) (*Note: reinstatement works to be completed in plain concrete only*);
- Footpath replacement works from Woodrow Street to 112 Saltwater Creek Road (including bus stop area and area in front of 112 Saltwater Creek Road);



PROJECT SCOPE OF WORKS (CONTD):

- Removal of tree on the footpath between 110 and 112 Saltwater Creek Road;
- Subsoil drainage works;
- Reconnection of stormwater to outlets;
- Road pavement reinstatements work against excavated kerb areas;
- Topdressing and turfing of disturbed areas.

The traffic management plan that will be put in place for the duration of the construction period will allow for one lane of Saltwater Creek Road to be closed. Additionally when works commence in Woodrow Street a one lane/one way traffic arrangement with traffic travelling in a westerly direction will be put in place.

INDICATIVE PROJECT MILESTONES

January 2025	Final Design
Feb/July 2025	Construction Period
Aug 2025	Project Completion

Note: Project milestones are subject to weather and may change.

Kerb and Channel and Footpath Replacement – Woodrow Street and Saltwater Creek Road (Wilson Street to 118 Saltwater Creek Road)

