

Sectional Road Pavement Rehabilitation – Bauple Drive (Stratford Road to 700m South)

PROJECT:

This project provides sectional road pavement rehabilitation works in Bauple Drive from Stratford Road to 700m south on Bauple Drive.

The road rehabilitation works are being undertaken as a result of Council's ongoing asset inspection program which identified that the road was showing signs of pavement failure and distress.

PROJECT ESTIMATE:

\$1.3M

PROJECT SCOPE OF WORKS:

The project scope is as follows:

- Pavement widening to a 9m wide road surface;
- Vegetation management works;
- Excavation of existing bitumen surfacing;
- Extension of existing culverts;
- Installation of new pavement material;
- Bitumen resurfacing;
- Pavement marking and signage.

The traffic management plan that will be put in place for the duration of the construction period will be developed prior to works commencing.



INDICATIVE PROJECT MILESTONES

February 2025	Final Design
May/September 2025	Construction Period
October 2025	Project Completion

Note: Project milestones are subject to weather and may change.

Sectional Road Pavement Rehabilitation – Bauple Drive (Stratford Road to 700m South)



