

Netherby Road Culvert Replacement

PROJECT:

This project provides for the replacement of the existing culverts located on Netherby Road over Oakey Creek (approx 5km south west of Tiaro).

These works are being undertaken as a result of damage sustained during the TC Alfred flooding event in March 2025.

PROJECT ESTIMATE:

\$1.76M (This project is funded through the Federal and State Government's Disaster Recovery Funding Arrangements)

PROJECT SCOPE OF WORKS:

The project scope allows for the following:

- Vegetation/tree removal;
- Construction of two-lane side track;
- Demolition of existing culverts and headwalls;
- Installation of 2 x 3300 x 2700 Reinforced Concrete Box Culverts with 3300 Link Slab;
- Installation of multi-cell headwall;
- Installation of fish baffles;
- Construction of concrete batter and rock protection to edge of concrete batter;
- Pavement reinstatement;
- Linemarking and signage;
- Topsoiling/turfing of disturbed areas.



The provision of a two-lane side track (under reduced speed limit) will allow for continued use of Netherby Road for the duration of the construction period.

INDICATIVE PROJECT MILESTONES

March 2026	Final Design
March 2026	Tender Period
June/Sept 2026	Construction Period
Oct 2026	Project Completion

Note: Project milestones are subject to contract and weather and may change.

Netherby Road Culvert Replacement

